




Weld-After-Backfill: A Growing Industry Practice

**Bob Buchanan
Ralph Warner
Dennis Dechant**

Weld-After-Backfill



- W-A-B is a growing practice in steel water pipeline construction
- W-A-B sequence:
 - Assemble the joint in the trench
 - Weld the outside of the joint if specified
 - Apply the exterior coating(s)
 - Backfill the pipe
 - Remove interior bracing
 - Weld the inside joint at a later time



W-A-B History



- W-A-B has been used for the past 16 years on projects ranging from 36" pipe in San Diego to 120" pipe in Charlotte.
- Safety, Constructability and Pipeline Integrity are principle reasons to use W-A-B
- 1st project using W-A-B was the Lake Texoma 72" line built in 1989
- More than 50 major projects have been constructed using W-A-B in the past 16 years

Sample Listing of W-A-B Projects




SAMPLE LISTING OF PROJECTS USING WELD AFTER BACKFILL SEQUENCE							
	Steel Water Pipe Manufacturers Technical Advisory Committee, AWWA, 2004						
	Compiled by: Weld After Backfill Task Group, Ralph Warner, Chair (National Welding Corp.)						
State	Project	Year	Footage	Dia.	Wall (t.)	Owner	Engineer
California							
	Flume Replacement Project	2000	24,000'	42" & 48"	0.250"	Helix Water District	Montgomery Watson
	San Diego Pipeline #2 Segment A	2002	25,000'	48"	0.375"	City of San Diego	Wilson Engineering
	Miramar WTP Improv. Project	2002	3,200'	36" & 48"	0.250"	City of San Diego	CDM
	Miramar Road Pipeline	2002	25,000	36"	.19" to .63"	City of San Diego	ASL
Colorado							
	East Cherry Creek Transmission Main	2003	59,000	54" & 48"	.400"	ECCV Sanitation District	Camp Dresser & McKee
	Chimney Park Pipeline	03/2003	11,000	60"	0.313	Greeley CO	Boyle Engineering
	Pleasant Valley Pipeline ***	2003	46,000	67"	.283"	No Colo WCD	CH2MHill
Florida							
	Replacement of 54" & 60" Main	1993	18,000	60"	0.375"	Pinellas County	Greeley & Hansen
	Replacement of 54" & 60" Main	1995	45,000	60"	0.375"	Pinellas County	
	Cypress Bridge A	1994	33,000	66"	0.340"	West Coast Reg. Water	Montgomery Watson
	North Central Hillsborough Intertie #1	2001	32,000	84"	0.445"	Tampa Bay Water	Greeley & Hansen
	North Central Hillsborough Intertie #2	2001	32,000	84"	0.445"	Tampa Bay Water	Greeley & Hansen
	Groundwater Treatment Plant	2001	16,000	84" & 72"	0.445"	Tampa Bay Water	Parsons Engineering
	South Central Hillsborough Intertie #1	2001	35,000	72"	0.370"	Tampa Bay Water	Camp Dresser & McKee
	South Central Hillsborough Intertie #2	2001	35,000	72"	0.375"	Tampa Bay Water	Camp Dresser & McKee
	Tampa Bay Reservoir	2003	10,000	84"	.438" & 1.00"	Tampa Bay Water	Greeley & Hansen / HDR
	Tampa Bay Reservoir Pipeline	2003	32,000	84"	.438"	Tampa Bay Water	Greeley & Hansen
Georgia							
	Lawrenceville - Lake Lanier Trans	1997	45,000	78"	0.625"	Gwinnett County	Metcalf & Eddy
	Shoal Creek RWI #1	2003	4,000	72"	0.375"	Gwinnett County	Parsons Engineering
	Shoal Creek RWI #2	2003	28,000	72"	0.375"	Gwinnett County	Parsons Engineering
Oregon							
	Sunset Highway 26 Transmission Line	1999	25,000	48"	0.250"	Tualatin Valley Water Dist.	Consulting Engineers, EES Inc.
	No. Hills Water Transmission Main	2003	9,800	36"	0.250"	City of Corvallis	City of Corvallis
New Jersey							
	Jersey City Aqueduct Relocation	2005	7,600	72"	.410"	N.J. Turnpike Authority	The RBA Group
New York							
	Sithe/Independence Main	1993	18,000	36"	0.375"	City of Oswego	Nussbaumer & Clark
North Carolina							
	120" Raw Water Line	1998	29,000	120"	0.675	Charlotte-Mecklenburg MUD	Hazen & Sawyer
Texas							
	Lake Texoma Pipeline *	1989	30,000	72"	0.313"	North Texas MWD	
	Cooper Lake Water Transmission 3	1992	58,000	84"	0.375"	North Texas MWD	Freese & Nichols
	Surface Water Treatment Program	1994	6,000	66	0.375"	City of Houston	Lockwood, Andrews & Newnam
	Plano - McKinney Phase 3 **	1996	25,000	96"	0.438"	North Texas MWD	Freese & Nichols
	East Water Program, Contract 2A	1996	8,000	84"	0.375"	City of Houston	Lockwood, Andrews & Newnam
	84" Water Main, Contract 2B-1	1998	2,933	84"	0.423"	City of Houston	Lockwood, Andrews & Newnam
	Lake Chapman Water Project	2001	174,000	72"	0.438"	City of Irving	CH2MHill/M.W.H.
	Carrizo Design 2B	2003	32,000	60"	Various	San Antonio Water System	Lockwood, Andrews & Newnam
	Carrizo Design 2	2003	41,000	60"	Various	San Antonio Water System	CEC
	6B-1	2003	5,000	84"	.438"	Houston	Lockwood, Andrews & Newnam
	Ella Blvd	2003	8,000	54"	.283"	Houston	Lockwood, Andrews & Newnam
	Hempstead Highway	2003	16,000	54"	.283"	Houston	Lockwood, Andrews & Newnam
	Williamson Cnty 48" Waterline Reloc.	2005	5,000	48"	.269"	Williamson Cnty - BrazosRA	Lockwood, Andrews & Newnam
Utah							
	Sandridge Pipeline	1999	9,000	48"	0.188, 0.313"	Weber Basin WCD	Bowen & Collins
	15000 South Water Transmission Line	2001	22,000	48"	0.375"	Jordan Valley WCD	Boyle Engineering
	Point of The Mtn Aqueduct *****	2005	63,000	60"	.025" - .040"	Metro Water Dist of SLC	CH2MHill
Virginia							
	Military Highway Route 13	1993	12,000	48"		VA Dept of Transportation	HDR Engineers

Constructability – Open Trench




- Conventional Construction
- Pipe exposed to thermal stress
- Risk of flooding & floating pipe
- Interrupted backfill
- Welding in critical path



Constructability – Closed Trench



- Weld After Backfill Sequence
- No Thermal Stresses
- No risk of floating pipe
- Consistent Backfill
- Installation independent of welding



Safety Considerations




- W-A-B provides better and safer access to work inside the pipe
- Provides shortened open trench exposures
- Benefits the contractor, designer and owner




Safety - Internal Access



Access in 78" Pipe w/ Vertical Brace
1/12th Scale



Access in 60" Pipe w/ Six-way Bracing
1/12th Scale



Weld-After-Backfill



- Challenges the exterior field joint coating
- AWWA (SWPMTAC) has been trying to bring the standards up to date with field practice
- Research by Canusa-CPS, National Welding and Northwest Pipe done to determine best practices

Weld-After-Backfill Trials



- Trials conducted to evaluate the effects of welding on the external field joint coating
- Common field welding techniques evaluated
- Several coating system designs tested
- Objective to optimize current practices
- Observations, results and conclusions determined variables that affect performance

Weld-After-Backfill Trials




- Systems applied to a 48" OD, .250" wall pipe
- Standard heat-shrink sleeves alone
- Standard heat-shrink sleeves with underlays
- Buried with compacted sand backfill
- Welded – FCAW, SMAW
- Excavated and inspected
 - Visual assessment
 - Holiday test
 - Adhesion test

Coating Systems Tested



- Heat-Shrinkable Sleeves of various design
 - Backing and adhesive type variables
- Underlay materials evaluated
 - Various types or no underlay
- System design evaluated



Typical Welding Methods



- FCAW (Flux Core Arc Welding)
 - High production benefit
 - Requires more equipment - shielding gases, wire feeder
 - Requires more expertise to weld effectively
- SMAW (Shielded Metal Arc Welding)
 - Simplest (most common) welding method
 - Generally less efficient than FCAW
 - Commonly done by “rig” welders

Test Assembly



Backfill Box over Pipe



Two Bell Ends with 'Pup' between them




Two Pipe Joints



Weld-After-Backfill Trials



- Systems applied to a 48" OD, .250" wall pipe
 - Standard heat-shrink sleeves alone
 - Standard heat-shrink sleeves with underlays
 - Applied, buried & welded internally



Heat-Shrink Sleeve Installation



Backfilling Prior to Welding




Internal Welding



Weld-After-Backfill Trials




- Temperature measured inside the pipe & under the sleeve




Temp Stick Photos




Before Welding



After Welding



Temp Stick Data



Heat Input



$$\frac{\text{Voltage} \times \text{Amperage} \times 60}{\text{Travel Speed}} = (\text{Joules/in.})$$

	Welding Process	Number of Passes	Voltage	Amperage	Travel Speed (in./min.)	Heat Input (Joules/in.)
Trial 1	FCAW	1	26	200	8.6	36,279
	SMAW	2	28	110	6.7	27,582
Trial 2	FCAW	1	24	180	8.9	29,124
	SMAW	2	29	110	7.5	25,520
Trial 3	FCAW	1	22	200	10.0	26,400
	SMAW	2	30	150	7.1	38,298
Trial 4	FCAW	1	20	180	9.2	23,478
	SMAW	2	30	150	7.0	38,571
Trial 5	FCAW	1	24	220	7.9	39,950
	SMAW	2	27	140	6.5	34,892
Trial 6	FCAW	1	24	190	8.4	32,727
	SMAW	2	27	140	5.7	39,789
Trial 7	FCAW	1	23	190	9.3	28,285
	SMAW	2	26	130	6.8	29,824
Trial 8	FCAW	1	23	190	9.3	28,285
	SMAW	2	27	140	5.2	43,448

Note: All SMAW Heat inputs were calculated on the second pass values

Welding Heat Input




Trial 7	Voltage	Amperage	Travel Speed (in. / min.)	Heat Input (Joules / in.)
FCAW	23	190	9.3	28,285
SMAW - 1st Pass	26	130	10.7	19,013
SMAW - 2nd Pass	26	130	6.8	29,824

- Travel Speed is the most critical factor to heat applied during welding
- Gaps in the pipe joint cause slower progress and therefore greater heat input
- Quantity of metal deposited in a pass also affects heat input

Weld-After-Backfill Trials



- Temperature inside pipe & under sleeve measured



- Conclusion: High heat has an affect on the coating

Eight Trials Completed



Table 1a - Trials 1 to 4

	Trial 1		Trial 2		Trial 3		Trial 4	
	Underlay	Sleeve	Underlay	Sleeve	Underlay	Sleeve	Underlay	Sleeve
Product	n/a	KLON	WC 20R	AQW-HS	n/a	AQW-HS	WC 20R	AQW-FF
Backing Thickness	n/a	0.036	0.016	0.036	n/a	0.036	0.016	0.025
Adhesive Thickness	n/a	0.065	0.025	0.045	n/a	0.045	0.025	0.050
Total Thickness	n/a	0.101	0.041	0.081	n/a	0.081	0.041	0.075
Observations	PE backing visibly affected by heat but no initial holiday. Adhesive affected resulting in lower adhesion strength. Evaluation after 3 months exposure showed movement in the visible damage, which would have resulted in a holiday.		PE backing visibly affected by heat but no initial holiday. Adhesive affected resulting in lower adhesion strength. Evaluation after 3 months exposure showed no change.		PE backing visibly affected by heat with a burn through at a point near the pipe bottom. Adhesive affected resulting in lower adhesion strength. Evaluation after 3 months exposure showed no change.		Slight affect from heat with backfill material "impression" in backing. No initial holiday. Evaluation after 3 months exposure showed no change.	

Table 1b - Trials 5 to 8


	Trial 5		Trial 6		Trial 7		Trial 8	
	Underlay	Sleeve	Underlay	Sleeve	Underlay	Sleeve	Underlay	Sleeve
Product	Test-UL	AQW-HS	CRP-O	AQW-HS	CLS	AQW-HS	AQW-HS	AQW-HS
Backing Thickness	0.032	0.036	0.032	0.036	0.032	0.036	0.036	0.036
Adhesive Thickness	0.025	0.045	0.045	0.045	0.030	0.045	0.045	0.045
Total Thickness	0.057	0.081	0.077	0.081	0.062	0.081	0.081	0.081
Observations	PE backing visibly affected by heat as noted by a crease in the backing along the HAA ¹ . Underlay material burned but outer sleeve intact. No initial holiday due to double thickness.		PE backing visibly affected by heat as noted by a crease in the backing along the HAA ¹ . Underlay adhesive affected resulting in lower adhesion strength at steel interface. No initial holiday due to double thickness.		Slight crease or sleeve recovery along the step down due to heat release through the gap in the bell & spigot. Modest reduction in adhesion through the HAA ¹ . No initial holiday.		Visibly affected by heat as noted by a crease along the step down due to a gap in the bell & spigot. Minor reduction in adhesion through the HAA ¹ . Burn through near the bottom due to a large gap in the step down and a rock in the backfill.	

1 - Heat affected area

Trial Photos – Effects of Heat



Step down edge recovery due to heat effect at bell and spigot interface




Crease in backing due to surface temp above the weld bead

Trial Photos – Adhesion Testing



Peel testing, note adhesive differences through heat affected area

Trial Photos – Effects of Heat



Peel test – note underlay adhesion



PE backing visibly affected but adhesion good

Field Trial: San Antonio Water System



Observations - Backings



- Heated backings expand, then contract as they cool. Backfill pressure keeps the sleeve in place.
- Polyethylene backings in a single layer system will be affected as noted such that some reduction in mechanical properties may occur
- Excessive gap in the pipe joint may allow heat flow-through which can affect the sleeve at the bell edge. Keeping joints within tolerance very important to coating integrity.

Observations



- Performance of a system is a result of:
 - adhesive's resistance to flow & off-gas during welding
 - the resistance of a backing to expand and contract
- Some systems perform better because:
 - adhesives with higher molecular weight fractions have a lower propensity to off-gas and flow
 - HDPE backings have more resistance to expansion & contraction

Recommendations



- Tight joint gap tolerances
- Some specifiers request filler materials to bridge the stepdown. Heat tolerant fillers are then required such that they do not affect weld quality
- Supply an underlay material that combines a thick low stretch HDPE backing and a butyl-based adhesive
- Use a standard product as the outer sleeve

Recommendations



- Recommended system incorporates a specially designed underlay material and standard outer sleeve
- Single layer systems possible and have been used successfully on thicker wall pipe
- An extra layer provides assured protection
- The growing use of WAB has created the need to address the construction method on an industry wide level

Recommendations




- At recent SWPMTAC meetings, WAB text was proposed for inclusion in relevant standards.
- Requires that the system maintain minimum performance
- In a demo of a single sleeve, a peel test over the heat-affected area will yield a reduction in performance but...
- It may still meet the requirements of the standard

Recommendations



- When an underlay material is used, the underlay adhesive may be degraded but acts as sacrificial, so the outer sleeve can be considered to be intact.



Weld-After-Backfill



- The W-A-B construction method has advantages versus conventional welding
 - Improved safety during construction
 - Fewer obstructions inside pipe
 - Less risk from open trench outside pipe
 - Improved Pipeline Integrity
 - Reduced thermal stress
 - Consistent backfill
 - Improved Production
 - Installation & Welding on parallel paths
 - No interruptions for expansion joints



Weld-After-Backfill. Weld-After-Backfill is the sequence of assembling a welded joint, welding the outside joint (if required), applying the exterior coating(s), backfilling the pipe, then welding the inside joint at a later time (where internal welding is safe and practical). Welding inside field joints after backfill (Weld-After-Backfill sequence) is an acceptable practice provided the requirements of all applicable AWWA standards are followed. Consult with the manufacturers and all other responsible parties regarding recommended products, installation and backfill procedures required for the Weld-After-Backfield sequence. At the request of the purchaser, the coating manufacturer will provide testing or historical information to verify that the exterior joint coating will retain performance requirements as per the applicable standard throughout the heat affected area.